

GOVERNMENT OF ANDHRA PRADESH
ABSTRACT

Medium Irrigation – Kadapa District – Buggavanka Project – Improvements to Buggavanka project earthen dam in C.K.dinne (M), Kadapa District – Administrative approval for an amount of Rs.45.35 lakhs – Accorded – Orders – Issued.

IRRIGATION & CAD (PW:M&MI-R.III.2) DEPARTMENT

G.O.Ms.No. 51

Dated:09.08.2012

Read the following:-

- 1.From the Engineer-In-Chief, Medium Irrigation, Hyderabad, Lr.No.ENC/Med/DCE-3/OT-5/AEE/BVP/SDSI/12, dated:02.03.2012.
- 2.Govt.Memo.No.5838/M&MI-R.III/A2/2012-1, dated:21.03.2012.
- 3.From the Engineer-In-Chief, Medium Irrigation, Hyderabad, Lr.No. ENC/Med/DCE-3/OT-5/AEE/BVP/SDSI/12, dated:11.05.2012.
- 4.Govt.Memo.No.5838/M&MI-R.III/A2/2012, dated:07.06.2012.
- 5.From the Engineer-In-Chief, Medium Irrigation, Hyderabad, Lr.No. ENC/Med/DCE-3/OT-5/AEE/BVP/SDSI/12, dated:21.06.2012.

ORDER:

The Engineer-In-Chief, Medium Irrigation, Hyderabad in his letter dated:2.3.2012 read above, has stated that the Buggavanka Project is a Medium Irrigation Project located at about 10 Km's of south of Kadapa town and it was completed during the year 2000. The capacity of the reservoir is 0.504 TMC. The developed ayacut under the project is 9,700 acres in Khariff season. Buggavanka Project is also visiting place to the people of Kadapa and its surrounding villages.

2. The Engineer-In-Chief has submitted an estimate for "improvements to Buggavanka Project earthen dam in C.K.dinne (M), Kadapa District" for Rs.45.35 Lakhs duly following the suggestions made by the Chief Engineer, Central Designs Organization with the following provisions:

1. Jungle Clearance on earthen bund.
2. White washing to the spillway and its surroundings.
3. Turfing to the berms and slopes of the earthen bund which is not covered with revetment.
4. Maintenance of Turfing for 12 months.
5. Provision towards VAT @ 4%, and provision towards labour Cess @ 1%.
6. Provision towards tender publication charges, Xerox and Photographic charges.

3. The Engineer-In-Chief has further reported that the estimate is prepared with current SSR 2011-12 and worked out to Rs.45.35 Lakhs.

4. The work has been recommended by the State Dam Safety Inspection Team vide inspection note dated:07.12.2011.

5. The Engineer-In-Chief, Medium Irrigation has therefore requested that administrative approval for the work "Improvements to Buggavanka Project Earth Dam in C.K.dinne (M), Kadapa District" for Rs.45.35 lakhs may be accorded.

(P.T.O.)

::2::

6. In the circumstances reported by the Engineer-In-Chief, Medium Irrigation, Hyderabad in the letters read above, Government after careful examination hereby accord administrative approval for an amount of Rs.45.35 lakhs (rupees forty five lakhs and thirty five thousand only) for the estimate for the work "Improvements to Buggavanka Project Earth Dam in C.K.dinne (M), Kadapa District" as per the details annexed to this order.

7. The expenditure sanctioned in para(6) above shall be debited to the Head of Account "4701 M&MI-03-108 Buggavanka Project – GH 11 Normal State Plan – SH 26 D & A – 530/531 O.E."

8. The Engineer-In-Chief, Medium Irrigation, Hyderabad shall take further necessary action accordingly.

9. This order issues with concurrence of Finance(Expr.PW) Department vide their U.O.No.17992/639/A1/Exp.PW/12, dated:18.07.2012.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

B. ARAVINDA REDDY
PRINCIPAL SECRETARY TO GOVERNMENT

To
The Engineer-In-Chief, Medium Irrigation, Hyderabad.

Copy to:

The Accountant General, A.P., Hyderabad.

The Director of Works & Accounts, Hyderabad.

The Finance (Expr.PW)Department.

The OSD to Minister(M&MI).

The PS to Principal Secretary (AR).

SF/SCs.

//FORWARDED::BY ORDER//

SECTION OFFICER

Annexure to G.O.Ms.No. 51, Irrigation & CAD(M&MI-R.III.2)Dept.,
dated:09-08-2012

| Sl.No. | Description of work | Amount in Rs. |
|--------|--|---------------|
| 1. | clearing thin jungle growth (more than 50% open space) including bushes up to 30cms/ parthenium and other weeds including burning disposing off the same as directed etc., complete | 29,700 |
| 2. | white washing two coats with surya cem for walls to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials including cost of all materials labour charges and incidental such as scaffolding lift charges and over heads and contractor's profit complete for finished item of work | 3,30,220 |
| 3. | Providing and laying Hariyala or other approved quality turfing sods for the slopes of earthen embankments over 20mm th sand backing including cost of all materials machinery, labour including preparing surface, spreading sand watering for 15 days etc.. complete with initial lead up to 1 km and all lifts. | 26,82,900 |
| 4. | maintenance of turfing for the period of 12 including cost of labour for watering keeping the turfing in slush grown and weed free condition etc complete. (284/100 sqm/1 month)=(2.84/1sqm/1 month) | 11,24,640 |
| | working items | 41,67,460 |
| 5. | add cess 1% on working items (on 41,67,460) | 41,675 |
| 6. | Provision for VAT & 4% | 1,66,698 |
| 7. | Provision for preparation of tender schedule advertisement charges, "e" procurement charges etc. | 1,50,000 |
| 8. | Provision for photographic, video graphic, xerox charges and strainers | 9167 |
| | Total Rs.45,35,000/- (Rupees forty five lakhs and thirty five thousand only) | |

B. ARAVINDA REDDY
PRINCIPAL SECRETARY TO GOVERNMENT